

Start Here

Scan One Time Only

And

Copy for Multiple Numbers

HA-609

AND

HA-610

34

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICENATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM

FOR NPS USE ONLY

RECEIVED

DATE ENTERED

SEE INSTRUCTIONS IN HOW TO COMPLETE NATIONAL REGISTER FORMS
TYPE ALL ENTRIES -- COMPLETE APPLICABLE SECTIONS

1 NAME

HISTORIC

Little Falls Meeting House & Fallston Friends School House

AND/OR COMMON

2 LOCATION

STREET & NUMBER East side of Old Fallston Road
at Reckford Road

NOT FOR PUBLICATION

CITY, TOWN

CONGRESSIONAL DISTRICT

Fallston

VICINITY OF

First

STATE

Maryland

CODE
24COUNTY
HarfordCODE
025

3 CLASSIFICATION

CATEGORY

DISTRICT

X BUILDING(S)

STRUCTURE

SITE

OBJECT

OWNERSHIP

PUBLIC

X PRIVATE

BOTH

PUBLIC ACQUISITION

IN PROCESS

BEING CONSIDERED

STATUS

X OCCUPIED

UNOCCUPIED

WORK IN PROGRESS

ACCESSIBLE

X YES: RESTRICTED

YES: UNRESTRICTED

NO

PRESENT USE

AGRICULTURE

MUSEUM

COMMERCIAL

PARK

EDUCATIONAL

PRIVATE RESIDENCE

ENTERTAINMENT

X RELIGIOUS

GOVERNMENT

SCIENTIFIC

INDUSTRIAL

TRANSPORTATION

MILITARY

OTHER

4 OWNER OF PROPERTY

NAME

Little Falls Monthly Meeting of Friends, Inc. c/o Alice Rensberg

STREET & NUMBER

2130 Fallston Road

CITY, TOWN

Fallston

VICINITY OF

STATE

Maryland

21047

5 LOCATION OF LEGAL DESCRIPTION

COURTHOUSE,
REGISTRY OF DEEDS, ETC.

Clerk of the Circuit Court

STREET & NUMBER

40 South Main Street

CITY, TOWN

Bel Air

STATE

Maryland

6 REPRESENTATION IN EXISTING SURVEYS

TITLE

DATE

FEDERAL STATE COUNTY LOCAL

DEPOSITORY FOR
SURVEY RECORDS

CITY, TOWN

STATE

7 DESCRIPTION

CONDITION

—EXCELLENT
☒ GOOD
—FAIR

—DETERIORATED
—RUINS
—UNEXPOSED

CHECK ONE

—UNALTERED
☒ ALTERED

CHECK ONE

☒ ORIGINAL SITE
—MOVED DATE _____

DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

Little Falls Friends Meeting House is located on the east side of Old Fallston Road (Maryland Route 152) at its junction with Reckford Road in Fallston, Harford County, Maryland.

Constructed in 1843, it is a sprawling one-story stone structure with shallow-pitched gable roof and a shed-roofed porch across the west and south facades. The walls are of random-coursed fieldstone laid with large granite quoins and brick jack arches over the windows.

The west (main) facade is five bays across with two double doors filling the central bay. This entrance is flanked on either side by two 12/12, double-hung sash windows with three-panel shutters. Each leaf of the doors has four panels, three horizontal ones above a vertical. There is a four-light transom above each set of doors. The porch has square, chamfered posts resting on a concrete floor. The porch roof and the main roof are sheathed with slate shingles.

The south end is wide, but contains only two bays, a 12/12 window on the west and a double door with transom on the east. This facade has been stuccoed but two datestones in the gable remain visible. The larger stone reads 1843, while the smaller stone above reads 1773. The latter was saved from the earlier meeting house, which was taken down when this one was built. The shed-roofed porch continues around the south end and at the east end of it is a privy with a four-panel door opening onto the porch. This frame structure, covered with clapboards, is now used for storage. Steps lead from the porch to the ground in front of the door; below this east end of the porch and privy, a small basement has been carved out for the modern furnace.

The east facade, overlooking the cemetery, has two windows centered in the end wall.

The north end has a window to the west and door to the east identical to those on the south end. A datestone of 1843 is located in the gable. There is a frame privy to the east of the door and an entrance porch sheltering both the door to this and the door to the meeting house. This privy has clapboards on the north and west sides, but vertical board siding on the east. It has a batten ~~door~~ and appears later than the privy on the south end.

A brick stove chimney rises from the gable peak at each end of the building. A modern brick furnace fence stands to the east of the original chimney at the south end; it was constructed flush with the wall without disturbing the stonework or stucco. Each of these 12/12 sash windows has a good; they are the only windows without shutters. This facade is also stuccoed. A small, modern frame shed has been built against the south end of this wall.

The interior of the meeting house is divided into two spaces by two pulley-operated, counter-balanced horizontal board partitions. The bottom half of the partition slides down into horizontal board wainscoting while the upper panel slides up through the ceiling into the attic. The south room was for the men, the north for women.

The ceiling is probably a later alteration and is composed of narrow unpainted boards. The original wide board floors remain but are concealed by a wall-to-wall floor covering.

SEE CONTINUATION SHEET #1.

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM

FOR NPS USE ONLY

RECEIVED

DATE ENTERED

Little Falls Friends Meeting House
Harford County

CONTINUATION SHEET Maryland

ITEM NUMBER 7 PAGE 1

(DESCRIPTION, continued)

Each side of the meeting house has a series of benches on graduated risers facing the front (east). At the front of the rooms facing west, are three shorter benches on two risers which were for the elders.

The benches are original. In the east corner of the south room is a corner cupboard built for the storage of books. Although not built in, it has been here a long while and is filled with old books. Narrow strips of wood are nailed several inches apart on either side of the cupboard, allowing the shelf height to be adjusted. The bookcase is about seven feet tall and has two five-panel doors.

Behind the meeting house is a cemetery which dates from the earlier structure on this site. The first graves here are unmarked as was the custom among Quakers at that time. The earliest marker is that of William Amos, founder of Little Falls Meeting. Amos was buried at his farm, but his body and slate marker were later moved to the cemetery. The inscription reads: Wm. Amos d. 1759. A later memorial stone is inscribed William Amos of England. A cast-iron fence surrounds the graveyard, containing about an acre and a half.

To the south of the meeting house is a one-story frame structure with gable roof built in three sections. The easternmost addition was put on during the renovation of the building in 1975 (James T. Wollon, Jr., Architect). The central section was added after 1898, and the original was built in the 1850s as a school.

The mid-19th century school building consists of one large room with three bays on the south facade and two on the north and west. The east wall was taken out when the 1898 addition was made. This section is covered with clapboards and rests on a rough stone foundation. Batten shutters have been restored to the structure based on an old shutter found under the building. Windows have 6/6 sash. The entrance on the south now consists of one batten door sheltered by a shed-roofed porch with rough log posts on a concrete base. There was originally another door immediately to the right of the present one; this was apparently removed when the first addition was made as the opening is covered with the same boarding found used on that section. An exterior chimney of brick on a concrete foundation is situated between the two earlier parts on the south facade. A metal stove pipe extends from the top of the brick stack which is broad with stepped bricks at the roofline and a plain narrower stack above and below.

The post-1898 portion is a one-bay structure sheathed with German siding and sitting on a concrete block foundation. The 6/6 windows here also have new batten shutters. The 1975 addition contains a kitchen and two bathrooms and is slightly wider than the earlier sections. It sits on a concrete block foundation and is covered with clapboards. ; smaller windows have matching batten shutters.

SEE CONTINUATION SHEET #2.

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**

FOR NPS USE ONLY

RECEIVED

DATE ENTERED

Little Falls Friends Meeting House

Harford County

CONTINUATION SHEET Maryland

ITEM NUMBER 7

PAGE 2

(DESCRIPTION, continued)

The interior of the 1850s and post-1898 sections are one open space with two chamfered posts and a foot-high plaster wall at the ceiling marking the former outside east wall of the earlier section. The floor of the addition was at platform level until it was lowered in the recent renovation. The woodwork in both sections is very plain, though different in form. The most interesting thing about the interior is the gently arched ceiling. The story goes that the teacher in the 1850s insisted on a vaulted ceiling so he could teach astronomy. This vaulted ceiling was extended into the post-1898 section when it was built.

Stored in the school building is a wood stove that was used in the meeting house. It is a cast-iron pot-bellied stove. Molded into the iron is the following: "Champion No 132, The Wehrle Co., Makers, Newark, Ohio."

B SIGNIFICANCE

PERIOD	AREAS OF SIGNIFICANCE -- CHECK AND JUSTIFY BELOW			
PREHISTORIC	<input type="checkbox"/> ARCHEOLOGY-PREHISTORIC	<input type="checkbox"/> COMMUNITY PLANNING	<input type="checkbox"/> LANDSCAPE ARCHITECTURE	<input checked="" type="checkbox"/> RELIGION
1400-1499	<input type="checkbox"/> ARCHEOLOGY-HISTORIC	<input type="checkbox"/> CONSERVATION	<input type="checkbox"/> LAW	<input type="checkbox"/> SCIENCE
1500-1599	<input type="checkbox"/> AGRICULTURE	<input type="checkbox"/> ECONOMICS	<input type="checkbox"/> LITERATURE	<input type="checkbox"/> SCULPTURE
1600-1699	<input checked="" type="checkbox"/> ARCHITECTURE	<input checked="" type="checkbox"/> EDUCATION	<input type="checkbox"/> MILITARY	<input type="checkbox"/> SOCIAL/HUMANITARIAN
1700-1799	<input type="checkbox"/> ART	<input type="checkbox"/> ENGINEERING	<input type="checkbox"/> MUSIC	<input type="checkbox"/> THEATER
1800-1899	<input type="checkbox"/> COMMERCE	<input type="checkbox"/> EXPLORATION/SETTLEMENT	<input type="checkbox"/> PHILOSOPHY	<input type="checkbox"/> TRANSPORTATION
1900-	<input type="checkbox"/> COMMUNICATIONS	<input type="checkbox"/> INDUSTRY	<input type="checkbox"/> POLITICS/GOVERNMENT	<input type="checkbox"/> OTHER (SPECIFY)
		<input type="checkbox"/> INVENTION		

SPECIFIC DATES 1843 BUILDER/ARCHITECT _____

STATEMENT OF SIGNIFICANCE

SIGNIFICANCE

Little Falls Friends Meeting house is a fine example of the Quaker architecture of the area comprised of southeastern Pennsylvania, northern Maryland, and northern Virginia. It is the largest one-story meeting house to survive in Maryland and retains all its original details (except perhaps the ceiling). It has the characteristic features of the Friends' meeting houses, including two entrance doors and a sliding partition dividing the interior into the men's and women's sides.

Little Falls Meeting had a school connected with it from circa 1749 until the early 20th century. At one time this Meeting ran as many as three Quaker schools simultaneously. The school building survives here as a reminder of this Meeting's continuing interest in education.

The Little Falls Meeting itself dates from the mid-18th century. It was founded by William Amos, a Harford County man who determined his own religious beliefs and, when he found they coincided with those of the Quakers, began the Meeting here. Amos is buried in the graveyard here.

HISTORY

Quakerism flourished in Virginia and Maryland between 1655 and 1775, when many Friends moved from Pennsylvania. Friends settled on the Western Run of Gunpowder River before 1675 and formed a monthly meeting in 1739. Friends met at Patapsco Forest on the Little Falls of Gunpowder River in Harford County in 1747. A handwritten account, "The Yearly, Quarterly, and Particular Meetings of the People Called Quakers in the Several Provinces of America", written in 1762, shows the Little Falls Meeting to be under the care of the Gunpowder Monthly Meeting.

The Little Falls Meeting appears to have been in operation long before the Monthly Meeting here was formed in 1815. In his History of Harford County, Preston writes:

William Amos, a resident, large land owner and officer in the militia of that county, was walking on his premises one Sabbath morning, when his meditations and their effect upon his mind were of that character that he called worship. Here he afterwards resorted from a sense of conviction and found satisfaction in the continuing of the practice. Finally, being joined by several of his neighbors, upon comparing notes and making inquiries, they found their views on religious matters coincided with Friends, and going twenty miles to the meeting at Gunpowder, in Baltimore County and their case being

SEE CONTINUATION SHEET #3.

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

FOR NPS USE ONLY

RECEIVED

DATE ENTERED

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM

Little Falls Friends Meeting house

Harford County

CONTINUATION SHEET Maryland

ITEM NUMBER 8

PAGE 3

(SIGNIFICANCE, continued)

favorably considered by that body, they were taken into membership. (p.195).

In 1749 Thomas Bond conveyed part of "Bond's Forest" to be laid out near the road including a house now built intended for a Meeting House for people called Quakers, to worship God in, and also a school house already built. The first meeting house on this site at Fallston was a small log cabin, which was used until 1773 when a stone building was erected. The present house was built in 1843 and incorporates the datestone of the 1777 house along with its own.

In a survey conducted by the Yearly Meeting at Lombard Street in 1853, the Little Falls Meeting is shown to have had 53 Quaker children and three schools, all of which were taught by Friends. In 1871 Little Falls is listed as one school of three in the Baltimore Quarterly Meeting. (Forbush: 1972; p. 54).

Little Falls is a Hicksite Meeting, being a part of those Quakers greatly influenced by the preaching of Elias Hicks, who journeyed through this area between 1797 and 1829. He advocated Christian rationalism combined with the Quietist emphasis on the Inner Light. Elias Hicks could not admit that all parts of the Bible were divinely inspired. He insisted that people could not know the holy scriptures unless they first recognized the spirit of God in themselves.

The Hicksites were in a position to attract individuals who could not accept the fundamentalist view of the Bible, but Bliss Forbush states that :

a weakness of the Hicksites was their heterogeneous nature. Many members had no settled convictions concerning Quakerism. Most were birthright members and, out of habit, conformed to the customs of the Quietist period. They were united in desiring to maintain these customs, recoiled from what seemed to them to be the intolerance of all orthodoxy and held to the doctrine of the Inner Light. They more slowly moved away from their Quietist ways, enlarged their previous religious and philanthropic activities, but being less aggressive, did not grow in numbers until the modern time. (p.69).

Membership of this meeting through the years is as follows:

<u>JUST BEFORE CIVIL WAR</u>	<u>1880</u>	<u>1900</u>	<u>1910</u>	<u>1950</u>	<u>1960</u>	<u>1970</u>
325	205	152	115	, 70	58	57

UNITED STATES DEPARTMENT OF THE INTERIOR
HERITAGE CONSERVATION AND RECREATION SERVICE

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**

FOR HCRS USE ONLY

RECEIVED

DATE ENTERED

Little Falls Friends Meeting House
Harford County

CONTINUATION SHEET Maryland

ITEM NUMBER 9

PAGE 4

MAJOR BIBLIOGRAPHICAL REFERENCES

Forbush, Bliss. A History of the Baltimore Yearly Meeting of Friends. Sandy Spring, Maryland: Baltimore yearly meeting of Friends, 1972.

Preston, Walter W. History of Harford County. Baltimore: Press of the Sun Book Office, 1901.

Rose, Harold Wickliffe, The Colonial Houses of Worship in America. 1963.

Werline, Albert Warwick. Problems of Church and State in Maryland. 1948.

Wright, C. Milton. Our Harford Heritage. By the Author, 1967.

Pamphlet, "Little Falls Friends' Meeting". Available at the meeting house, Fallston, Maryland.

The Aegis, 8/19/76. p. B1.

MAJOR BIBLIOGRAPHICAL REFERENCES

SEE CONTINUATION SHEET #4.

GEOGRAPHICAL DATA

ACREAGE OF NOMINATED PROPERTY 3.374 acres

QUADRANGLE NAME Jarrettsville

QUADRANGLE SCALE 1:24000

UTM REFERENCES

A 18 3791100 4374020
ZONE EASTING NORTHING

B
ZONE EASTING NORTHING

C

D

E

F

G

H

VERBAL BOUNDARY DESCRIPTION

See boundary of Little Falls Monthly Meeting of Friends, Inc. property on enclosed plat map #27-61 (Deed GRG 586/572).

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE	CODE	COUNTY	CODE
-------	------	--------	------

STATE	CODE	COUNTY	CODE
-------	------	--------	------

FORM PREPARED BY

NAME / TITLE Pamela James, National Register Coordinator/
Susan M. Deeney, Field Historian

ORGANIZATION Maryland Historical Trust/
Historic District Commission

DATE

Sept. 1978/September 1976

STREET & NUMBER 21 State Circle/
45 S. Main Street

TELEPHONE

(301) 269-2438/838-6000 ext. 207

CITY OR TOWN Annapolis/
Bel Air

STATE

Maryland 21401/21014

STATE HISTORIC PRESERVATION OFFICER CERTIFICATION

THE EVALUATED SIGNIFICANCE OF THIS PROPERTY WITHIN THE STATE IS:

NATIONAL

STATE

LOCAL X

As the designated State Historic Preservation Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the National Park Service.

STATE HISTORIC PRESERVATION OFFICER SIGNATURE

[Signature] 2-6-80

TITLE STATE HISTORIC PRESERVATION OFFICER

DATE

FOR NPS USE ONLY


I HEREBY CERTIFY THAT THIS PROPERTY IS INCLUDED IN THE NATIONAL REGISTER

DATE

ATTEST: KEEPER OF THE NATIONAL REGISTER

DATE

CHIEF OF REGISTRATION



20 FEET
DATUM OF 1929

1 MILE
4000 5000 6000 7000 FEET
1 KILOMETER

Jarrettsville Quad

QUADRANGLE LOCATION

STOCKTON 2 MI.
5.9 MI TO U.S. 40

INTERIOR—GEOLOGICAL SURVEY, WESTON, VIRGINIA

BAGLEY 0.2 MI.
BALTIMORE 20 MI.

KINGSVILLE 3.8 MI.
BALTIMORE 20 MI.
381000 E

ROAD CLASSIFICATION

Heavy-duty	Light-duty
Medium-duty	Unimproved dirt

 U.S. Route
 State Route

JARRETTSVILLE

N3930—W7622.517

MARYLAND HISTORICAL TRUST

HA - 609

610

INVENTORY FORM FOR STATE HISTORIC SITES SURVEY

1306094210
1306104402

1 NAME

HISTORIC

Little Falls Meeting House & Fallston Friends School House

AND/OR COMMON

Little Falls Friends Meeting House

2 LOCATION

c/o Herbert Hoopes
Forest Hill, Maryland

STREET & NUMBER

RD # 1 Old Fallston Road

First

CITY, TOWN

Fallston

VICINITY OF

CONGRESSIONAL DISTRICT

STATE

Maryland

COUNTY

Harford

3 CLASSIFICATION

CATEGORY

☐ DISTRICT
☐ BUILDING(S)
☐ STRUCTURE
☐ SITE
☐ OBJECT

OWNERSHIP

☐ PUBLIC
☐ PRIVATE
☐ BOTH
PUBLIC ACQUISITION
☐ IN PROCESS
☐ BEING CONSIDERED

STATUS

☐ OCCUPIED
☐ UNOCCUPIED
☐ WORK IN PROGRESS
ACCESSIBLE
☐ YES: RESTRICTED
☐ YES: UNRESTRICTED
☐ NO

PRESENT USE

☐ AGRICULTURE
☐ COMMERICAL
☐ EDUCATIONAL
☐ ENTERTAINMENT
☐ GOVERNMENT
☐ INDUSTRIAL
☐ MILITARY
☐ MUSEUM
☐ PARK
☐ PRIVATE RESIDENCE
☐ RELIGIOUS
☐ SCIENTIFIC
☐ TRANSPORTATION
☐ OTHER

4 OWNER OF PROPERTY

NAME

Little Falls Monthly Meeting of Friends, Inc Telephone #:

STREET & NUMBER

RD # 1, Old Fallston Road

CITY, TOWN

Fallston

VICINITY OF

STATE, zip code

Maryland 21047

5 LOCATION OF LEGAL DESCRIPTION

COURTHOUSE,

REGISTRY OF DEEDS, ETC. Clerk of Circuit Court

STREET & NUMBER

40 S. Main Street

CITY, TOWN

Bel Air

STATE

Maryland

Liber #: 586

Folio #: 566

6 REPRESENTATION IN EXISTING SURVEYS

TITLE

DATE

☐ FEDERAL ☐ STATE ☐ COUNTY ☐ LOCAL

DEPOSITORY FOR
SURVEY RECORDS

CITY, TOWN

STATE

7 DESCRIPTION

CONDITION

☐ EXCELLENT
☒ GOOD
☐ FAIR

☐ DETERIORATED
☐ RUINS
☐ UNEXPOSED

CHECK ONE

☒ UNALTERED
☐ ALTERED

CHECK ONE

☒ ORIGINAL SITE
☐ MOVED DATE _____

DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

This is a one story, stone masonry building, 5 bays by 2. The center bay consists of double doors separated by a post. Each door leads into a separate room which is used for women's meetings and men's meetings. The roof is of slate and has narrow, plain eaves. There is a chimney at each inside gable end. These are of brick and are flush inside. Two new brick flues at either end rise outside the walls. A one story porch extends around the south and west sides, and it is paved with stone and brick. Windows are 12 lights over 12 and have shutters with moulded panels.

Inside, the meeting house is panelled and the customary meeting house partition consists of two panelled sections counter balanced between two posts. The panels divide so that the upper panel slides up into an area between the ceiling and the roof, the lower panel drops down into a space below floor level, opening the area up into one room.

Fallston Friends School House HA - 610

This little frame school house is covered with hand split boards measuring approximately 4 feet long. The overlap is uneven and measures approximately 4 inches. The rectangular building faces south. It has a low pitched, slate covered roof, which is gable flank. The building is one story, and 3 bays by 2. An addition to the north is the same height and width but is 2 bays by 1. An exterior brick chimney rises out of the south wall. This accomodates a Stove inside. Windows are 6 lights over 6. There is a Shed roofed entrance porch over the south door way.

CONTINUE ON SEPARATE SHEET IF NECESSARY

8 SIGNIFICANCE

PERIOD	AREAS OF SIGNIFICANCE -- CHECK AND JUSTIFY BELOW			
<input type="checkbox"/> PREHISTORIC	<input type="checkbox"/> ARCHEOLOGY-PREHISTORIC	<input type="checkbox"/> COMMUNITY PLANNING	<input type="checkbox"/> LANDSCAPE ARCHITECTURE	<input checked="" type="checkbox"/> RELIGION
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> ARCHEOLOGY-HISTORIC	<input type="checkbox"/> CONSERVATION	<input type="checkbox"/> LAW	<input type="checkbox"/> SCIENCE
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> AGRICULTURE	<input type="checkbox"/> ECONOMICS	<input type="checkbox"/> LITERATURE	<input type="checkbox"/> SCULPTURE
<input checked="" type="checkbox"/> 1600-1699	<input type="checkbox"/> ARCHITECTURE	<input checked="" type="checkbox"/> EDUCATION	<input type="checkbox"/> MILITARY	<input checked="" type="checkbox"/> SOCIAL/HUMANITARIAN
<input checked="" type="checkbox"/> 1700-1799	<input type="checkbox"/> ART	<input type="checkbox"/> ENGINEERING	<input type="checkbox"/> MUSIC	<input type="checkbox"/> THEATER
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> COMMERCE	<input type="checkbox"/> EXPLORATION/SETTLEMENT	<input type="checkbox"/> PHILOSOPHY	<input type="checkbox"/> TRANSPORTATION
<input type="checkbox"/> 1900-	<input type="checkbox"/> COMMUNICATIONS	<input type="checkbox"/> INDUSTRY	<input type="checkbox"/> POLITICS/GOVERNMENT	<input type="checkbox"/> OTHER (SPECIFY)
		<input type="checkbox"/> INVENTION		

SPECIFIC DATES

BUILDER/ARCHITECT

STATEMENT OF SIGNIFICANCE

The significance of this building lies in its antiquity as an organized Quaker meeting, and architecturally, as an excellent example of typical Quaker architecture of Pennsylvania and northeastern Maryland. It is in its original condition save for the addition of utilities.

Quakerism flourished in Virginia and Maryland between 1655 and 1775, when many Friends moved from Pennsylvania. Friends settled on the Western Run of Gunpowder River before 1675 and became a Monthly Meeting in 1739. Friends met at Patapsco Forest on the Little Falls of Gunpowder River in Harford County in 1747. Little Falls Monthly Meeting was formed in 1815. A handwritten account, "The Yearly, Quarterly, and Particular Meetings of the People Called Quakers in the Several Provinces of America", written in 1762, shows the Little Falls Meeting to be under the care of the Gunpowder Monthly Meeting.

The Little Falls Meeting appears to have been in operation long before the Monthly Meeting was formed in 1815. Preston tells us in his History of Harford County (p. 195)

"William Amos, a resident, large land owner and officer in the militia of that county, was walking on his premises one Sabbath morning, when his meditations and their effect upon his mind were of that character that he called worship. Here he afterwards resorted from a sense of conviction and found satisfaction in the continuing of the practice. Finally, being joined by several of his neighbors, upon comparing notes and making inquiries, they found their views on religious matters coincided with Friends, and going twenty miles to the meeting at Gunpowder, in Baltimore County, and their case being favorably considered by that body, they were taken into membership."

In 1749, Thomas Bond conveyed part of "Bond's Forest" to be laid out near the road including a house now built intended for a Meeting House for people called Quakers, to worship God in, and also a school house already built. The first meeting house on this site at Fallston was a small log cabin which was used until 1773 when a stone building was erected. The present one was built in 1843. At one end of the present building is a datestone of 1777. At the other end is one for 1843.

In a survey conducted by the Yearly Meeting at Lombard Street in 1853, the Little Falls Meeting is shown to have had 53 Quaker children and three schools, all of which were taught by Friends. In 1871, Little Falls is listed as one school of three in the Baltimore Quarterly Meeting. (Forbush: 1972; p.54).

Little Falls is a Hicksite Meeting, being a part of those Quakers greatly influenced by the preaching of Elias Hicks who journeyed through this area between 1797 and 1829. He advocated Christian rationalism combined with the Quietist emphasis on the Inner Light. Elias Hicks could not admit that all parts of the Bible were divinely inspired. He insisted that people could not know the holy scriptures unless they first reconized the the spirit of God in themselves.

CONTINUE ON SEPARATE SHEET IF NECESSARY

9 MAJOR BIBLIOGRAPHICAL REFERENCES

Forbush, Bliss; A History of the Baltimore Yearly Meeting of Friends, 1972, Baltimore Yearly Meeting of Friends, Sandy Spring, Maryland.
Preston, Walter W.; History of Harford County, 1901, Press of the Sun Book Office, Balt. pp. 193 - 197
Rose, Harold Wickcliffe; The Colonial Houses of Worship in America, 1963. p. 185.

CONTINUE ON SEPARATE SHEET IF NECESSARY

10 GEOGRAPHICAL DATA

ACREAGE OF NOMINATED PROPERTY 300 ft. x 450 feet

VERBAL BOUNDARY DESCRIPTION

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE

COUNTY

STATE

COUNTY

11 FORM PREPARED BY

NAME / TITLE

Susan M. Deeney, Field Historian

DATE

ORGANIZATION

Historic District Commission

9/3/76

TELEPHONE

STREET & NUMBER

45 S. Main Street

838-6000 ext 207

STATE

CITY OR TOWN

Bel Air

Maryland

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature, to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 Supplement.

The Survey and Inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

RETURN TO: Maryland Historical Trust
The Shaw House, 21 State Circle
Annapolis, Maryland 21401
(301) 267-1438

Bliss Forbush states that "a weakness of the Hicksites was their heterogeneous nature. Many members had no settled convictions concerning Quakerism. Most were birthright members and, out of habit, conformed to the customs of the Quietist period. They were united in desiring to maintain these customs, recoiled from what seemed to them to be the intolerance of all orthodoxy and held to the doctrine of the Inner Light. They more slowly moved away from their Quietist ways, enlarged their previous religious and philanthropic activities, but being less aggressive, did not grow in numbers until the modern time." (P 69).

The Hicksites were in a position to attract individuals who could not accept the fundamentalist view of the Bible.

Membership of this meeting through the years is as follows:

<u>Just Before Civil War</u>	<u>1880</u>	<u>1900</u>	<u>1910</u>	<u>1950</u>	<u>1960</u>	<u>1970</u>
325	205	152	115	70	58	57

BIBLIOGRAPHY

- Werline, Albert Warwick; Problems of Church and State in Maryland, 1948. pp. 29,67,75.
Wright, C. Milton; Our Harford Heritage, 1967. pp. 220 - 222.





Little Falls Friends Meeting House HA-609
Fallston, MD
Southeast
May, 1977
Susan M. Deeney



HA-60

Little Falls Friends Meeting School House
HA-610
Fallston, MD
North
May, 1977
Susan M. Deeney



Little Falls Friends Meeting House HA-609
Fallston, MD
Southeast
May, 1977
Susan M. Deeney

End Here

Scan One Time Only
And
Copy for Multiple Numbers

HA-609

AND

HA-610